

| MHC#   | Feature  | Milepost | Proposed Action | Proposed Project Activity   |             |    |  |
|--|--|----------|-----------------|---|-------------|----|--|
| <b>Newly identified contributing resource (not included on SUD.R inventory form)</b>   |  |          |                 |   |             |    |  |
|  | Electric switch box                                    | 19.75    | R&R             | Remove & reset  |             |    |  |
| <b>Contributing resources on SUD.R inventory form that could not be located by SHC/Spies, but were located by Eversource/DCR</b> |  |          |                 |   |             |    |  |
|  | Farm Crossing (2 concrete & rebar posts)               | 18.79    | Avoid           | Outside limit of work   |             |    |  |
|  | Culvert 125B   | 18.73    | Extend          | Extend existing pipe to maintain vernal pool hydrology.   | Remove      | 2  |  |
| <b>Contributing resources on SUD.R inventory form that were located by both SHC/Spies and Eversource/DCR</b>                     |  |          |                 |   |             |    |  |
| SUD.936  | Culvert 126A   | 18.96    | Avoid           | Clear out sediment  | Replace     | 2  |  |
| SUD.937  | Milepost N-85/B-19                                     | 19.00    | Avoid           | Outside limit of work   | Rehab       | 1  |  |
| SUD.938  | Culvert 126B   | 19.06    | Avoid           | Cut vegetation on northeast wingwall that is causing collapse (no grubbing).                        | Extend      | 1  |  |
| SUD.939  | Rail Rest  | 19.21    | R&R             | Remove & reset  | Avoid       | 38 |  |
| SUD.940  | Culvert 126D   | 19.22    | Avoid           | Outside limit of work   | Avoid / R&R | 14 |  |
| SUD.942  | Battery Well for Distant Approach Signal               | 19.26    | Avoid/R&R       | Avoid; if not possible, remove and reset.   | R&R         | 13 |  |
| SUD.941  | Distant Approach Signal                                | 19.26    | R&R             | Remove & reset  | Total       | 71 | * including 4 archaeological sites, two resources included on Spies' inventory but were not located nor given MHC inventory numbers, and one new resource (electric switch box) that was identified recently by CHG/VHB. |
| SUD.943  | Signal Relay Box                                       | 19.37    | R&R             | Remove & reset  |             |    |  |
| SUD.901  | Bridge 127   | 19.47    | Replace         | Replace superstructure (top two courses of stone abutments to be removed; other courses to remain). |             |    |  |
| SUD.944  | Poured Concrete base for Signal Relay Box/Battery Well | 19.60    | Avoid/R&R       | Avoid; if not possible, remove and reset.   |             |    |  |
| SUD.945  | Culvert 127A   | 19.70    | Replace         | Replace with 24" ductile iron pipe ("DIP") with concrete headwall.                                  |             |    |  |
| SUD.946  | Whistle Post   | 19.73    | Avoid           | Outside limit of work   |             |    |  |
| SUD.282  | Section Tool House                                     | 19.75    | Avoid           | Outside limit of work   |             |    |  |
| SUD.947  | Concrete base for Auto Highway Flashers                | 19.76    | Avoid           | Outside limit of work   |             |    |  |
| SUD.949  | Signal Relay Box (mast only)                           | 19.76    | Avoid           | Outside limit of work   |             |    |  |

|         |  |       |           |   |  |  |  |
|---------|--|-------|-----------|---|--|--|--|
| SUD.948 | Concrete base for Auto Highway Flashers                      | 19.76 | Avoid/R&R | Avoid; if not possible, remove and reset. |  |  |  |
| SUD.950 | Culvert 127B   | 19.87 | Avoid     | Outside limit of work                     |  |  |  |
| SUD.951 | Concrete Bases for Highway Signal                            | 19.97 | Avoid     | Outside limit of work                     |  |  |  |
| SUD.952 | Concrete Sign Post   | 19.98 | Avoid/R&R | Avoid; if not possible, remove and reset. |  |  |  |
| SUD.396 | South Sudbury Station  | 19.99 | Avoid     | Avoid                                     |  |  |  |
| SUD.954 | 3 Switch Stands  | 20.00 | Avoid/R&R | Avoid; if not possible, remove and reset. |  |  |  |
| SUD.955 | Concrete bases & steel posts for Signal/Electrical boxes (5) | 20.00 | R&R       | Remove & reset                            |  |  |  |
| SUD.953 | Milepost   | 20.00 | R&R       | Remove & reset                            |  |  |  |
| SUD.956 | Diamond junction with Framingham & Lowell RR                 | 20.02 | R&R       | Remove & reset                            |  |  |  |
| SUD.957 | Wood whistle/stop sign post                                  | 20.02 | Avoid/R&R | Avoid; if not possible, remove and reset. |  |  |  |
| SUD.959 | Concrete Base for Signal E2                                  | 20.07 | Avoid/R&R | Avoid; if not possible, remove and reset. |  |  |  |
| SUD.958 | Signal Relay Box   | 20.07 | Avoid/R&R | Avoid; if not possible, remove and reset. |  |  |  |
| SUD.960 | Rail Rest  | 20.09 | Avoid/R&R | Avoid; if not possible, remove and reset. |  |  |  |
| SUD.961 | Signal Relay Box   | 20.13 | Avoid     | Outside limit of work                     |  |  |  |
| SUD.962 | Culvert 127C   | 20.14 | Avoid     | Outside limit of work                     |  |  |  |
| SUD.963 | Signal Relay Box   | 20.34 | R&R       | Remove & reset                            |  |  |  |
| SUD.964 | Wood Post  | 20.34 | Avoid     | Outside limit of work                     |  |  |  |
| SUD.965 | Tall Concrete Sign Post                                      | 20.39 | Avoid/R&R | Avoid; if not possible, remove and reset. |  |  |  |
| SUD.966 | Culvert 127D   | 20.44 | Avoid     | Outside limit of work                     |  |  |  |
| SUD.967 | Rail Rest  | 20.55 | Avoid/R&R | Avoid; if not possible, remove and reset. |  |  |  |
| SUD.968 | Signal Relay Box   | 20.59 | R&R       | Remove & reset                            |  |  |  |
| SUD.969 | Whistle Post   | 20.63 | Avoid/R&R | Avoid; if not possible, remove and reset. |  |  |  |
| SUD.970 | Culvert 127E   | 20.75 | Avoid     | Outside limit of work                     |  |  |  |
| SUD.972 | Signal Relay Box   | 20.79 | Avoid     | Outside limit of work                     |  |  |  |
| SUD.971 | Crossing Sign Base   | 20.79 | R&R       | Remove & reset                            |  |  |  |

|           |  |           |                 |   |  |  |  |
|-----------|--|-----------|-----------------|---|--|--|--|
| SUD.974   | Battery Well for Interlocking Signal #M208 | 20.80     | Avoid/R&R       | Avoid; if not possible, remove and reset.   |  |  |  |
| SUD.973   | Distant Approach Interlocking Signal #M208 | 20.80     | Avoid           | Outside limit of work   |  |  |  |
| SUD.975   | Rail Rest                                  | 20.98     | R&R             |   |  |  |  |
| SUD.976   | Milepost B21 N83                           | 21.00     | Avoid           | Outside limit of work   |  |  |  |
| SUD.977   | Whistle Post                               | 21.13     | Avoid           | Outside limit of work   |  |  |  |
| SUD.978   | Signal Relay Box                           | 21.16     | Avoid/R&R       | Avoid; if not possible, remove and reset.   |  |  |  |
| SUD.979   | Culvert 127F                               | 21.18     | Avoid           | Outside limit of work   |  |  |  |
| SUD.980   | Wood Post North Side of ROW                | 21.29     | R&R             |   |  |  |  |
| SUD.981   | Auto Highway Flashers/Signal Relay Cabinet | 21.35     | Avoid           | Outside limit of work   |  |  |  |
| SUD.982   | Wood Post, south side of ROW               | 21.36     | Avoid           | Outside limit of work   |  |  |  |
| SUD.983   | Culvert 127G                               | 21.40     | Avoid           | Outside limit of work   |  |  |  |
| SUD.984   | Culvert 127H                               | 21.51     | Avoid           | Cut two 12" trees that are causing wingwall damage (no grubbing).   |  |  |  |
| SUD.985   | Culvert 127I                               | 21.58     | Avoid           | Clear out debris on north end.  |  |  |  |
| SUD.986   | Whistle Post                               | 21.58     | Avoid           | Outside limit of work   |  |  |  |
| SUD.987   | Whistle Post                               | 21.66     | Avoid           | Outside limit of work   |  |  |  |
| SUD.988   | Rail Rest                                  | 21.94     | R&R             |   |  |  |  |
| SUD.989   | Milepost B22 N82                           | 22.00     | Avoid           | Outside limit of work   |  |  |  |
| SUD.990   | Culvert 127J                               | 22.05     | Avoid           | Outside limit of work   |  |  |  |
| SUD.991   | Whistle Post                               | 22.19     | Avoid           | Outside limit of work   |  |  |  |
| SUD.900   | Bridge 128                                 | 22.24     | Rehab           | Upgrade bridge deck to support trail & transmission line (removal of small portion of stone abutments on south side of both east and west abutments; other portions to remain ) |  |  |  |
| SUD.992   | Culvert 129A                               | 22.83     | Avoid           | Outside limit of work   |  |  |  |
| SUD.935   | Telegraph Poles                            | Throughou | Avoid           | Outside limit of work   |  |  |  |
| SUD.933   | Rails                                      | Throughou | Remove          | Remove  |  |  |  |
| SUD.934   | Wood Ties                                  | Throughou | Remove          | Remove  |  |  |  |
| SUD-HA-39 | East Sudbury Station Archaeological Site   | 18.84     | Avoid & protect | Protect with geotextile fabric & fill.  |  |  |  |

|  |   |        |                 |                       |  |  |  |
|--|---|--------|-----------------|-----------------------|--|--|--|
| SUD-HA-37  | Section Tool House Archaeological Site    | 19.75  | Avoid & protect | Outside limit of work |  |  |  |
| SUD-HA-26  | South Sudbury Station Archaeological Site | 19.99  | Avoid & protect | Outside limit of work |  |  |  |
| SUD-HA-38  | Wayside Inn Archaeological Site           | 21.90  | Avoid & protect | Outside limit of work |  |  |  |
| <b>Contributing resources on SUD.R inventory form that could not be located by SHC/Stacy Spies or Eversource/DCR</b> |   |        |                 |                       |  |  |  |
| XXX  | Signal Relay Box                          | 18.39? |                 |                       |  |  |  |
| XXX  | Culvert 126C                              | 19.28? |                 |                       |  |  |  |
| XXX  | Whistle Post                              | 22.?   |                 |                       |  |  |  |